LIVORA INTERIORS

QUOTATION

Miyapur, Hyderabad, Telangana 502034
Ph No : 8886767991

DATE : 05-08-2026 **QUOTE NO :** LQ-260805-942 **VALIDITY :** 15 days

CUSTOMER NAME & ADDRESS :

S.NO	DESCRIPTION	W	H	BOX	RATE	AMOUNT
Master Bedroom						
1	Wardrobe Box	5	8	40	₹1,500	₹60,000
2	MBR Bed	7	6	42	₹1,200	₹50,400
3	Head Board	8	4	32	₹600	₹19,200
4	Wall Panelling	8	5	40	₹800	₹32,000
5	Toilet Box	2	1	2	₹1,500	₹3,000
					Subtotal — Master Bedroom :	**₹1,64,600**
GBR Bedroom						
6	Wardrobe Box	7	8	56	₹1,500	₹84,000
7	Dresser With Mirror	3	6	18	₹1,500	₹27,000
8	Toilet Box	2	1	2	₹1,500	₹3,000
					Subtotal — GBR Bedroom :	**₹1,14,000**
CBR Bedroom						
9	Wardrobe Box	11.9	7	83.3	₹1,500	₹1,24,950
10	Loft Box	11.9	3	35.7	₹1,200	₹42,840
11	Toilet Box	2	1	2	₹1,500	₹3,000
					Subtotal — CBR Bedroom :	**₹1,70,790**
Hall						
12	TV Unit Box	3	8	24	₹1,500	₹36,000
13	TV Trolley Unit Box	1.5	8	12	₹1,500	₹18,000
14	TV Panelling Work	6	8	48	₹900	₹43,200
					Subtotal — Hall :	**₹97,200**
Crockery Unit						
15	Crockery Unit Box	6	7	42	₹1,500	₹63,000
					Subtotal — Crockery Unit :	**₹63,000**
Pooja Mandir						
16	Pooja Mandir Box	6	2	12	₹1,500	₹18,000
17	Pooja Mandir Panelling	6	6	36	₹1,200	₹43,200
18	Pooja Mandir Door	3	7	21	₹450	₹9,450

S.NO	DESCRIPTION	W	H	BOX	RATE	AMOUNT
					Subtotal — Pooja Mandir :	₹70,650
Kitchen						
19	Lower Cabinet Box	30.6	11.2	342.7	₹1,500	₹5,14,080
20	Loft & Wall Unit Box	24.3	10	243	₹1,200	₹2,91,600
21	Loft Box	34.6	10.9	377.1	₹1,200	₹4,52,568
					Subtotal — Kitchen :	₹12,58,248
False Ceiling						
22	*Gypsum Ceiling*	—	—	—	₹83,500	₹83,500
					Subtotal — False Ceiling :	₹83,500
Painting						
23	*Painting Work*	—	—	—	₹1,15,000	₹1,15,000
					Subtotal — Painting :	₹1,15,000
Electrical						
24	*Electrical Wiring & Material*	—	—	—	₹1,00,000	₹1,00,000
					Subtotal — Electrical :	₹1,00,000
					TOTAL :	**₹22,36,988**
					DISCOUNT :	**– ₹36,988**
					GRAND TOTAL :	**₹22,00,000**

AMOUNT IN WORDS : Rupees Twenty Two Lakh Only

NOTE — TERMS & CONDITIONS

1. Décor items not included
2. 40% payment as the project starts
3. 30% at mid way of the project
4. 20% at the time of handle installation
5. 10% at the time of final handover after snag list clearance
6. Full payment to be released at the time of handover
7. Any extra work other than the mentioned in the quote will be charged accordingly and should be paid in full (executed only after written approval)
8. Workmanship warranty of 1 year from the date of handover (excludes damage caused by misuse)
9. GST (if applicable) charged extra at the prevailing rate
10. Validity of this quotation: 15 days from the date of issue

MATERIAL SPECIFICATION

Plywood / Core Material: CENTURY CLUB PRIME 710 Grade BWP Plywood 16MM AND 6MM
Laminate: 1MM HGL / MATT / Fluted Laminate. Each Laminate cost not more than Rs. 2000

CUSTOMER NAME
Signature

For LIVORA INTERIORS
Authorized Signatory